Zeitschrift:	IABSE reports = Rapports AIPC = IVBH Berichte
Band:	60 (1990)
Artikel:	Composite beams with precast slabs and concrete cast in-situ
Autor:	Jianguo, Nie / Juhou, Wang / Vujofi, Arsenije
DOI:	https://doi.org/10.5169/seals-46470

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. <u>Mehr erfahren</u>

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. <u>En savoir plus</u>

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. <u>Find out more</u>

Download PDF: 12.07.2025

ETH-Bibliothek Zürich, E-Periodica, https://www.e-periodica.ch

Composite Beams with Precast Slabs and Concrete Cast In-Situ

Poutres mixtes à dalles et béton coulé sur place

Verbundträger mit vorfabrizierten Platten und Ortsbeton

Nie JIANGUO Wang JUHOU Zhengzhou Inst. of Techn. Zhengzhou, China

Arsenije VUJOFIĆ Dragan DRAGOVIĆ Titograd Univ. Titograd, Yugoslavia

SUMMARY

Tests of six simply supported composite steel-concrete beams with flanges composed of precast R.C. slabs and concrete cast in-situ were made to investigate the behaviour of this type of composite beam. An analytical approach for predicting more accurately the real carrying capacity of stud shear connectors in composite beams and ultimate strength of composite beams is proposed.

1. INTRODUCTION

As is known, it is very convenient for construction to use composite beams with flanges composed of precast R.C. slabs and concrete cast in-situ in practical engineering, because the precast R.C. slabs can not only become a part of the flanges of the beams, but also can be used as the forms of concrete cast in-situ,furthermore the concrete cast in-situ can make the floor structures behave well as a whole body. To add to our knowledge of how this type of composite beam behaves six specimens were tested and some analytical predictions were made.

2. SPECIMENS, TESTS AND COMMENTS ON THE TEST RESULTS

Six specimens shown in Fig.1 were designed with the same cross section, but with varying span (designated as L), shear span (designated as L_1 , in shear span there were 12 studs with diameter in 16mm for all beams), spacing of stud shear connectors, content ratio of transverse reinforcement (designated as d in percentage) and the strength of concrete. d includes the top transverse reinforcement and the bottom transverse reinforcement previously stretched out from the ends of the precast R.C. slabs without prefabricated slots for studs. The upper surface of the pre-cast R.C. slabs was kept in a natural state of casting to increase the shear resistance of the interaction. All beams were simply supported and loaded with two symmetrical point loads. Deflections, strains and relative slips were measured after each increment of load.

The main test results and the modes of failure are summarized in Tab.1, in which, the modes of failure are designated as F. for flexural failure, F.S.for flexural and longitudinally splitted failure and S. for longitudinally splitted failure.



Beam	L (mm)	L ₁ (mm)	a (%)	M·F·	Mut Mup	<u>Vu</u> V(1)
A 1	4500	1575	0.8	F.	1.05	1.20
A2	3800	1340	0.7	F.	1.03	1.19
A3	3000	1060	0.6	F.S.	1.07	1.15
A4	3000	1060	0.5	F.S.	1.01	1.08
B1	3000	1060	0.4	F.S	0.95	1.04
B2	3000	1060	0.3	s.	0.90	1.02

Table 1

Let Put represent the maximum load reached during a test. Flexural failure occured with the crashing of upper concrete in midspan, but no longitudinal cracks were monitored. For failure mode F.S., longitudinally splitted cracks occured along the top surface of concrete as the load was near Put, and then the concrete of compressive zone in midspan was crashed at Put. For failure mode S., longitudinally splitted cracks onset near the load points at 0.95 Put and then developed rapidly toward the ends of the beam, no crashing of concrete was observed. So it can be concluded that α equal to 0.7% is the lower bound to prevent the flanges from being splitted longitudinally. Although slots for study were not prefabricated, no local failure due to high shear resulted from study occured for all test beams, the onset and propagation of vertical cracks have the same feature as that of general composite beams with concrete flange fully cast in-situ. No relative slip between the precast R.C.slabs and concrete cast in-situ was observed, so the precast R.C.slabs and concrete of steel beam and concrete, and this is normal for composite beams. Tests have shown that study possess excellent behaviour of redistributing the shear in this type of composite beam.

Let Muprepresent the predicted ultimate strength of the beams by using simple theory of plasticity and Mut the test results. Comparing Mup with Mut(seeing Tab.1), we can conclude that α equal to 0.5% is the lower bound of the ratio of transverse reinforcement to make the beams develop the strength predicted by simple theory of plasticity.

3. PREDICTIONS FOR CARRYING CAPACITY OF STUDS AND STRENGTH OF COMPOSITE BEAMS

According to the test results, it is reasonable to assume the shear applied on each stud in shear span to be equal at Put. If the resultant tension existed in steel beam near the loaded point is T, and the amount of studs in shear span is n, we have:

Vu = T/n (1) where Vu denotes the lower bound of strength of studs at the ultimate limit state. To predict T by using the simple theory of plasticity is unreasonable obviously, because at load Put, not all part of the section of steel beam reached yield point (Fy). Taking the assumption of plane section, we can get:

 $T = \int_{A} \Phi Y E dA$

(2)

in which A denotes the whole section of steel beam, Φ the average curvature of the cross section measured from the tests, E the modulus of elasticity. $Y = \xi_0 / \Phi_1$, ξ_0 is the strain of the bottom fiber of the beam. If $\Phi Y E \ge F y$, putting $\Phi Y E = F y$. According to Eq.(2), we can get detail expressions for different state of strain distribution. Predictions (seeing Tab.1) from Eq.(1) and Eq(2) show that studs in this type of composite beam have higher capacity than that given by Ref.(1), so it can be concluded that the behaviour of studs in this type of composite beam are almost as same as that in general composite beams. On the basis of Eq.(2), we can also predict accurately the centroid of T by:

$D = Y - (\int_A \Phi \gamma^2 E dA)/T$

(3)

where D is the distance from the bottom of steel beam to the acted point of T. Using Eq.(2), Eq(3) and considering the conditions of equilibrium,we can predict more accurately the ultimate strength of composite beams without using simple theory of plasticity. It should be noted that the levels of neutral axis predicted by simple theory of plasticity for all test beams are near the interface, but tests have shown that vertical cracks developed into a higher depth of concrete flange at Put. The predictions by the methods presented above are well coincided with test. No attempt is made to discuss this problem in detail in the paper.

4. CONCLUSIONS

Composite steel-concrete beams with flanges composed of precast R.C.slabs without prefabricated slots for studs and concrete cast in-situ behave well as whole bodies. α has a nonnegligible effect on the ultimate strength and the modes of failure. The capacity of studs in this type of composite beam can be predicted by the method used for general composite beams. We can use the approach proposed in this paper to further study the prediction of ultimate strength of composite beams without using simple theory of plasticity.

REFERENCES

1. R.P. Johnson, Composite structures of steel and concrete, London, 1982.